



WA-6 (8309819) Troubleshooting Guide

No reception

- Verify antenna connector (Motorola Plug) is securely inserted into radio antenna port or pigtail.
- Verify white wire is fully extended.
- Verify white wire is attached to antenna connector (Motorola plug).
- Verify NO continuity between side of antenna connector (Motorola plug). Replace antenna if it is shorted.
- Verify continuity between white wire and tip of antenna connector (Motorola plug), then reconnect to radio. If no improvement replace antenna.